Construction of CC roads and other works at Abbigere colony balance roads in ward No.12, Shettyhalli Sub-division, Ward No. 12 - Shettyhalli. Sl. No. 03, G O No. 85 (Package No - DHZ 01).

Sl. No.	Description of Work	Chainage from	Chainage to	Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
	Dismantling Work (Footpath, Side Drains & Pre Cast Slabs)										
1	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH I Chapter 3(PW,P& IWTD SR 2018-19, Pg No 143 Item No. 19.1)										
	Desilting of Drain										
	1st cross road (RHS)	0.00	26.00	Cum	2	26.00	0.80	0.30	12.48		
	2nd cross road (RHS)	0.00	26.00	Cum	2	26.00	0.80	0.30	12.48		
	3rd cross road (RHS)	0.00	26.00	Cum	2	26.00	0.80	0.30	12.48		
	4th cross road (RHS)	0.00	24.70	Cum	2	24.70	0.80	0.30	11.86		
	5th cross road (RHS)	0.00	36.00	Cum	2	36.00	0.80	0.30	17.28		
	1st cros road (LHS)	0.00	45.00	Cum	2	45.00	0.80	0.30	21.60		
	2nd cros road (LHS)	0.00	70.00	Cum	2	70.00	0.80	0.30	33.60		
	3rd cros road (LHS)	0.00	65.00	Cum	2	65.00	0.80	0.30	31.20		
	5th cros road (LHS)	0.00	96.00	Cum	2	96.00	0.80	0.30	46.08		
	Earthwork for Kerb										
	2nd A cross road	0.00	25.00	Cum	2	25.00	0.20	0.10	1.00		
	1st cross road (RHS)	0.00	26.00	Cum	2	26.00	0.20	0.10	1.04		
	2nd cross road (RHS)	0.00	26.00	Cum	2	26.00	0.20	0.10	1.04		
	3rd cross road (RHS)	0.00	26.00	Cum	2	26.00	0.20	0.10	1.04		
	4th cross road (RHS)	0.00	24.70	Cum	2	24.70	0.20	0.10	0.99		
	5th cross road (RHS)	0.00	36.00	Cum	2	36.00	0.20	0.10	1.44		
	1st cros road (LHS)	0.00	45.00	Cum	2	45.00	0.20	0.10	1.80		
	2nd cros road (LHS)	0.00	70.00	Cum	2	70.00	0.20	0.10	2.80		
	3rd cros road (LHS)	0.00	65.00	Cum	2	65.00	0.20	0.10	2.60		
	4th cros road (LHS)	0.00	18.00	Cum	2	18.00	0.20	0.10	0.72		
	5th cros road (LHS)	0.00	96.00	Cum	2	96.00	0.20	0.10	3.84		
	7th cros road (LHS)	0.00	153.00	Cum	2	153.00	0.20	0.10	6.12		
	8th cros road (LHS)	0.00	56.00	Cum	2	56.00	0.20	0.10	2.24		
	9th cros road (LHS)	0.00	46.80	Cum	2	46.80	0.20	0.10	1.87		
	10th cros road (LHS)	0.00	28.5	Cum	2	28.50	0.20	0.10	1.14		
	Excavation For Dain										
	2nd A cross road	0.00	25.00	Cum	2	25.00	1.10	0.85	46.75		
	4th cros road (LHS)	0.00	18.00	Cum	2	18.00	1.10	0.85	33.66		
	7th cros road (LHS)	100.00	153.00	Cum	2	53.00	1.10	0.85	99.11		
	8th cros road (LHS)	0.00	56.00	Cum	2	56.00	1.10	0.85	104.72		
	9th cros road (LHS)	0.00	46.80	Cum	2	46.80	1.10	0.85	87.52		
	10th cros road (LHS)	0.00	28.50	Cum	2	28.50	1.10	0.85	53.30		
	RWH @ every 100m intervel			Cum	13	0.31		1.80	7.30		
	Total								**661.08**	**137.80**	**91,097.14**
2	KSRB 4-1.7: Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregtes @ 0.56cum, machine mixed, concrete laid in layers not exceeding 15 ems. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2 (PW,P& IWTD SR 2018-19 P-13, I-4.7)										
	M10 Concrete - PCC For drain										
	2nd A cross road	0.00	25.00	Cum	2	25	1.1	0.15	8.25		
	4th cros road (LHS)	0.00	18.00	Cum	2	18	1.1	0.15	5.94		
	7th cros road (LHS)	100.00	153.00	Cum	2	53	1.1	0.15	17.49		
	8th cros road (LHS)	0.00	56.00	Cum	2	56	1.1	0.15	18.48		
	9th cros road (LHS)	0.00	46.80	Cum	2	46.8	1.1	0.15	15.44		
	10th cros road (LHS)	0.00	28.50	Cum	2	28.5	1.1	0.15	9.41		
	M10 Concrete - PCC For Kerb										
	2nd A cross road	0.00	25.00	Cum	2	25.00	0.20	0.10	1.00		
	1st cross road (RHS)	0.00	26.00	Cum	2	26.00	0.20	0.10	1.04		

Sl. No.	Description of Work	Chainage from	Chainage to	Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
	2nd cross road (RHS)	0.00	26.00	Cum	2	26.00	0.20	0.10	1.04		
	3rd cross road (RHS)	0.00	26.00	Cum	2	26.00	0.20	0.10	1.04		
	4th cross road (RHS)	0.00	24.70	Cum	2	24.70	0.20	0.10	0.99		
	5th cross road (RHS)	0.00	36.00	Cum	2	36.00	0.20	0.10	1.44		
	1st cros road (LHS)	0.00	45.00	Cum	2	45.00	0.20	0.10	1.80		
	2nd cros road (LHS)	0.00	70.00	Cum	2	70.00	0.20	0.10	2.80		
	3rd cros road (LHS)	0.00	65.00	Cum	2	65.00	0.20	0.10	2.60		
	4th cros road (LHS)	0.00	18.00	Cum	2	18.00	0.20	0.10	0.72		
	5th cros road (LHS)	0.00	96.00	Cum	2	96.00	0.20	0.10	3.84		
	7th cros road (LHS)	0.00	153.00	Cum	2	153.00	0.20	0.10	6.12		
	8th cros road (LHS)	0.00	56.00	Cum	2	56.00	0.20	0.10	2.24		
	9th cros road (LHS)	0.00	46.80	Cum	2	46.80	0.20	0.10	1.87		
	10th cros road (LHS)	0.00	28.50	Cum	2	28.50	0.20	0.10	1.14		
	Total								**104.69**	**5714.97**	**5,98,294.15**
3	KSRRB M2200-5.12. Providing and laying Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.7 cum and fine aggregates @ 0.47 cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008. i) Upto 5 m height. (PW,P& IWTD SR 2018-19 P-227, I-28.7.12)										
	M25 Concrete - For drain Raft										
	2nd A cross road	0.00	25.00	Cum	2	25.00	0.90	0.15	6.75		
	4th cros road (LHS)	0.00	18.00	Cum	2	18.00	0.90	0.15	4.86		
	7th cros road (LHS)	100.00	153.00	Cum	2	53.00	0.90	0.15	14.31		
	8th cros road (LHS)	0.00	56.00	Cum	2	56.00	0.90	0.15	15.12		
	9th cros road (LHS)	0.00	46.80	Cum	2	46.80	0.90	0.15	12.64		
	10th cros road (LHS)	0.00	28.50	Cum	2	28.50	0.90	0.15	7.70		
	M25 Concrete - For drain Wall										
	2nd A cross road	0.00	25.00	Cum	4	25.00	0.15	0.60	9.00		
	4th cros road (LHS)	0.00	18.00	Cum	4	18.00	0.15	0.60	6.48		
	7th cros road (LHS)	100.00	153.00	Cum	4	53.00	0.15	0.60	19.08		
	8th cros road (LHS)	0.00	56.00	Cum	4	56.00	0.15	0.60	20.16		
	9th cros road (LHS)	0.00	46.80	Cum	4	46.80	0.15	0.60	16.85		
	10th cros road (LHS)	0.00	28.50	Cum	4	28.50	0.15	0.60	10.26		
	Total								**143.20**	**5775.37**	**8,27,027.78**
4	KSRRB M2200-6. Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification. MORTH Specification No.1600 & 2200 -do- TMT Bars Fe 500(PW,P& IWTD SR 2018-19, Pg No 229 Item No.28.8.2)										
	Quantity at 60 kg/ Cum of M25 concrete for Drains			Tonne	Drain concrete quantity			143.20			
									8.59		
	Total								**8.59**	**72,326.98**	**6,21,429.07**
5	Removing and resetting of footpath slab (PW,P & IWTD SR 2018-19, Item No.37.56, Page No.270)										
	For Drain Cover Slabs										
	1st cross road (RHS)	0.00	26.00	Sqm	2	26.00	0.90		46.80		
	2nd cross road (RHS)	0.00	26.00	Sqm	2	26.00	0.90		46.80		
	3rd cross road (RHS)	0.00	26.00	Sqm	2	26.00	0.90		46.80		
	4th cross road (RHS)	0.00	24.70	Sqm	2	24.70	0.90		44.46		
	5th cross road (RHS)	0.00	36.00	Sqm	2	36.00	0.90		64.80		
	1st cros road (LHS)	0.00	45.00	Sqm	2	45.00	0.90		81.00		
	2nd cros road (LHS)	0.00	70.00	Sqm	2	70.00	0.90		126.00		
	3rd cros road (LHS)	0.00	65.00	Sqm	2	65.00	0.90		117.00		
	5th cros road (LHS)	0.00	96.00	Sqm	2	96.00	0.90		172.80		

Sl. No.	Description of Work	Chainage from	Chainage to	Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
	Total								746.46		
	Considering 40% of resetting slabs								298.58	**208.82**	**62,350.31**
6	KSRB 15.2.2 : Providing ruled pointing 20 mm deep to stone slab pavements with cement mortar 1:3, 20mm deep, after raking joints nicely lining, including cost of materials, labour, curing complete as per specifications. (PW,P& IWTD SR 2018-19 P-115, I-15.8)										
	Pointing for resetting slabs										
	1st cross road (RHS)	0.00	26.00	Sqm	2	26.00	0.20		10.40		
	2nd cross road (RHS)	0.00	26.00	Sqm	2	26.00	0.20		10.40		
	3rd cross road (RHS)	0.00	26.00	Sqm	2	26.00	0.20		10.40		
	4th cross road (RHS)	0.00	24.70	Sqm	2	24.70	0.20		9.88		
	5th cross road (RHS)	0.00	36.00	Sqm	2	36.00	0.20		14.40		
	1st cros road (LHS)	0.00	45.00	Sqm	2	45.00	0.20		18.00		
	2nd cros road (LHS)	0.00	70.00	Sqm	2	70.00	0.20		28.00		
	3rd cros road (LHS)	0.00	65.00	Sqm	2	65.00	0.20		26.00		
	5th cros road (LHS)	0.00	96.00	Sqm	2	96.00	0.20		38.40		
	Total								**165.88**	**49.06**	**8,137.75**
7	Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortor including form work, lift charges , curing and concrtee finished surface on both sides etc, and complete as per the directions of Enginner in charges. (Data Rate)										
	For Drain Cover Slabs										
	2nd A cross road	0.00	25.00	Sqm	2	25.00	0.90		45.00		
	1st cross road (RHS)	0.00	26.00	Sqm	2	26.00	0.90		46.80		
	2nd cross road (RHS)	0.00	26.00	Sqm	2	26.00	0.90		46.80		
	3rd cross road (RHS)	0.00	26.00	Sqm	2	26.00	0.90		46.80		
	4th cross road (RHS)	0.00	24.70	Sqm	2	24.70	0.90		44.46		
	5th cross road (RHS)	0.00	36.00	Sqm	2	36.00	0.90		64.80		
	1st cros road (LHS)	0.00	45.00	Sqm	2	45.00	0.90		81.00		
	2nd cros road (LHS)	0.00	70.00	Sqm	2	70.00	0.90		126.00		
	3rd cros road (LHS)	0.00	65.00	Sqm	2	65.00	0.90		117.00		
	4th cros road (LHS)	0.00	18.00	Sqm	2	18.00	0.90		32.40		
	5th cros road (LHS)	0.00	96.00	Sqm	2	96.00	0.90		172.80		
	7th cros road (LHS)	0.00	153.00	Sqm	2	153.00	0.90		275.40		
	8th cros road (LHS)	0.00	56.00	Sqm	2	56.00	0.90		100.80		
	9th cros road (LHS)	0.00	46.80	Sqm	2	46.80	0.90		84.24		
	10th cros road (LHS)	0.00	28.50	Sqm	2	28.50	0.90		51.30		
	Total								**1335.60**	**1615.00**	**21,56,994.00**
8	KSRRB 300-50. Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by mechanical means attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per specifications. MORTH / Chapter 3 (PW,P & IWTD SR 2018-19, Item No. 19.56, Page No.146)										
	Road Formation										
	2nd A cross road	0.00	25.00	Sqm	1	25.00	4.00		100.00		
	5th A Cross Road	0.00	21.00	Sqm	1	21.00	2.00		42.00		
	1st cross road (RHS)	0.00	26.00	Sqm	1	26.00	6.50		169.00		
	2nd cross road (RHS)	0.00	26.00	Sqm	1	26.00	5.00		130.00		
	3rd cross road (RHS)	0.00	26.00	Sqm	1	26.00	5.10		132.60		
	4th cross road (RHS)	0.00	24.70	Sqm	1	24.70	5.50		135.85		
	5th cross road (RHS)	0.00	36.00	Sqm	1	36.00	5.20		187.20		
	1st cros road (LHS)	0.00	45.00	Sqm	1	45.00	6.50		292.50		
	2nd cros road (LHS)	0.00	70.00	Sqm	1	70.00	4.50		315.00		
	3rd cros road (LHS)	0.00	65.00	Sqm	1	65.00	5.80		377.00		
	4th cros road (LHS)	0.00	18.00	Sqm	1	18.00	7.50		135.00		
	5th cros road (LHS)	0.00	96.00	Sqm	1	96.00	5.80		556.80		
	7th cros road (LHS)	0.00	153.00	Sqm	1	153.00	5.40		826.20		
	8th cros road (LHS)	0.00	56.00	Sqm	1	56.00	5.40		302.40		
	10th cros road (LHS)	0.00	28.50	Sqm	1	28.50	5.30		151.05		
	Total								**3852.60**	**41.34**	**1,59,266.48**

Sl. No.	Description of Work	Chainage from	Chainage to	Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
9	KSRRB 300-48. Scarifying kankar / gravel / metal crust by mechanical means upto 150mm thick, disposal of stuff including cost of all labour charges, HOM complete as per specifications. MORTH / Chapter 3 (PW,P & IWTD SR 2018-19, Item No. 19.54, Page No.146)										
	Road Formation										
	2nd A cross road	0.00	25.00	Sqm	1	25.00	4.00		100.00		
	5th A Cross Road	0.00	21.00	Sqm	1	21.00	2.00		42.00		
	1st cross road (RHS)	0.00	26.00	Sqm	1	26.00	6.50		169.00		
	2nd cross road (RHS)	0.00	26.00	Sqm	1	26.00	5.00		130.00		
	3rd cross road (RHS)	0.00	26.00	Sqm	1	26.00	5.10		132.60		
	4th cross road (RHS)	0.00	24.70	Sqm	1	24.70	5.50		135.85		
	5th cross road (RHS)	0.00	36.00	Sqm	1	36.00	5.20		187.20		
	1st cros road (LHS)	0.00	45.00	Sqm	1	45.00	6.50		292.50		
	2nd cros road (LHS)	0.00	70.00	Sqm	1	70.00	4.50		315.00		
	3rd cros road (LHS)	0.00	65.00	Sqm	1	65.00	5.80		377.00		
	4th cros road (LHS)	0.00	18.00	Sqm	1	18.00	7.50		135.00		
	5th cros road (LHS)	0.00	96.00	Sqm	1	96.00	5.80		556.80		
	7th cros road (LHS)	0.00	153.00	Sqm	1	153.00	5.40		826.20		
	8th cros road (LHS)	0.00	56.00	Sqm	1	56.00	5.40		302.40		
	9th cross road LHS	0.00	46.80	Sqm	1	46.80	4.10		191.88		
	10th cros road (LHS)	0.00	28.50	Sqm	1	28.50	5.30		151.05		
	Total								**4044.48**	**25.44**	**1,02,891.57**
10	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications. MORTH I Chapter 3 (PW,P& IWTD SR 2018-19, Pg No 147 Item No.19.64)										
	Road Formation										
	2nd A cross road	0.00	25.00	Sqm	1	25.00	4.00		100.00		
	5th A Cross Road	0.00	21.00	Sqm	1	21.00	2.00		42.00		
	1st cross road (RHS)	0.00	26.00	Sqm	1	26.00	6.50		169.00		
	2nd cross road (RHS)	0.00	26.00	Sqm	1	26.00	5.00		130.00		
	3rd cross road (RHS)	0.00	26.00	Sqm	1	26.00	5.10		132.60		
	4th cross road (RHS)	0.00	24.70	Sqm	1	24.70	5.50		135.85		
	5th cross road (RHS)	0.00	36.00	Sqm	1	36.00	5.20		187.20		
	1st cros road (LHS)	0.00	45.00	Sqm	1	45.00	6.50		292.50		
	2nd cros road (LHS)	0.00	70.00	Sqm	1	70.00	4.50		315.00		
	3rd cros road (LHS)	0.00	65.00	Sqm	1	65.00	5.80		377.00		
	4th cros road (LHS)	0.00	18.00	Sqm	1	18.00	7.50		135.00		
	5th cros road (LHS)	0.00	96.00	Sqm	1	96.00	5.80		556.80		
	7th cros road (LHS)	0.00	153.00	Sqm	1	153.00	5.40		826.20		
	8th cros road (LHS)	0.00	56.00	Sqm	1	56.00	5.40		302.40		
	9th cross road LHS	0.00	46.80	Sqm	1	46.80	4.10		191.88		
	10th cros road (LHS)	0.00	28.50	Sqm	1	28.50	5.30		151.05		
	Total								**4044.48**	**6.36**	**25,722.89**
11	**CONCRETE PAVEMENT** **KSRRB M600- Cement Concrete Pavements** KSRRB M600-1.Providing and Constructing dry lean cement concrete mix CC 1:5:10 base with OPC 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @0.58cum over a prepared sub-base, coarse and fine aggregate conforming to IS: 383-2016,aggregate cement ratio not to exceed 15:1, Aggregate gradation after blending to be as per Table 600-1 ,optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a hatching plant, transported to site,laid with a paver, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications. Clause 601of MORTH V Revision and IS 456 Table-5 -do- with OPC at 150 kg/cum and coarse aggregate 0.86cum, fine aggregate 0.58cum using Concrete Batch mix Plant at 75 cum/hr capacity with fixed form paver. (PW,P& IWTD SR 2018-19 P-174, I-22.1.2)										
	2nd A cross road	0.00	25.00	cum	1	25.00	4.00	0.10	10.00		
	5th A Cross Road	0.00	21.00	cum	1	21.00	2.00	0.10	4.20		
	1st cross road (RHS)	0.00	26.00	cum	1	26.00	6.50	0.10	16.90		
	2nd cross road (RHS)	0.00	26.00	cum	1	26.00	5.00	0.10	13.00		
	3rd cross road (RHS)	0.00	26.00	cum	1	26.00	5.10	0.10	13.26		
	4th cross road (RHS)	0.00	24.70	cum	1	24.70	5.50	0.10	13.59		
	5th cross road (RHS)	0.00	36.00	cum	1	36.00	5.20	0.10	18.72		
	1st cros road (LHS)	0.00	45.00	cum	1	45.00	6.50	0.10	29.25		
	2nd cros road (LHS)	0.00	70.00	cum	1	70.00	4.50	0.10	31.50		

Sl. No.	Description of Work	Chainage from	Chainage to	Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
	3rd cros road (LHS)	0.00	65.00	cum	1	65.00	5.80	0.10	37.70		
	4th cros road (LHS)	0.00	18.00	cum	1	18.00	7.50	0.10	13.50		
	5th cros road (LHS)	0.00	96.00	cum	1	96.00	5.80	0.10	55.68		
	7th cros road (LHS)	0.00	153.00	cum	1	153.00	5.40	0.10	82.62		
	8th cros road (LHS)	0.00	56.00	cum	1	56.00	5.40	0.10	30.24		
	9th cross road LHS	0.00	46.80	cum	1	46.80	4.10	0.10	19.19		
	10th cros road (LHS)	0.00	28.50	cum	1	28.50	5.30	0.10	15.11		
	Total								**404.45**	**3944.51**	**15,95,348.82**
12	KSRRB M400-17. Providing, laying, spreading and compacting Crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No.406. (PW,P& IWTD SR 2018-19, Pg No 155, Item No. 20.18)										
	2nd A cross road	0.00	25.00	Cum	1	25.00	4.00	0.100	10.00		
	5th A Cross Road	0.00	21.00	cum	1	21.00	2.00	0.100	4.20		
	1st cross road (RHS)	0.00	26.00	cum	1	26.00	6.50	0.100	16.90		
	2nd cross road (RHS)	0.00	26.00	cum	1	26.00	5.00	0.100	13.00		
	3rd cross road (RHS)	0.00	26.00	cum	1	26.00	5.10	0.100	13.26		
	4th cross road (RHS)	0.00	24.70	cum	1	24.70	5.50	0.100	13.59		
	5th cross road (RHS)	0.00	36.00	cum	1	36.00	5.20	0.100	18.72		
	1st cros road (LHS)	0.00	45.00	cum	1	45.00	6.50	0.100	29.25		
	2nd cros road (LHS)	0.00	70.00	cum	1	70.00	4.50	0.100	31.50		
	3rd cros road (LHS)	0.00	65.00	cum	1	65.00	5.80	0.100	37.70		
	4th cros road (LHS)	0.00	18.00	cum	1	18.00	7.50	0.100	13.50		
	5th cros road (LHS)	0.00	96.00	cum	1	96.00	5.80	0.100	55.68		
	7th cros road (LHS)	0.00	153.00	cum	1	153.00	5.40	0.100	82.62		
	8th cros road (LHS)	0.00	56.00	cum	1	56.00	5.40	0.100	30.24		
	9th cross road LHS	0.00	46.80	cum	1	46.80	4.10	0.100	19.19		
	10th cros road (LHS)	0.00	28.50	cum	1	28.50	5.30	0.100	15.11		
	Total								**404.45**	**2001.28**	**8,09,413.69**
13	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum,Coarse and fine aggregate conforming to18:383-2016, with Superplastizer at 3 Its conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades,textured with texturing machine, and curing including cost of all materials, labour,hire charges of machineries,all lead & lift charges etc., complete as per specifications. -do- with OPC at 360 kg/cum and coarse aggregate 0.69cum, fine aggregate 0.46cum. (PW,P& IWTD SR 2018-19, Pg No 176 Item No. 22.6.1)										
	2nd A cross road	0.00	25.00	Cum	1	25.00	4.00	0.16	16.00		
	5th A Cross Road	0.00	21.00	Cum	1	21.00	2.00	0.16	6.72		
	1st cross road (RHS)	0.00	26.00	Cum	1	26.00	6.50	0.16	27.04		
	2nd cross road (RHS)	0.00	26.00	Cum	1	26.00	5.00	0.16	20.80		
	3rd cross road (RHS)	0.00	26.00	Cum	1	26.00	5.10	0.16	21.22		
	4th cross road (RHS)	0.00	24.70	Cum	1	24.70	5.50	0.16	21.74		
	5th cross road (RHS)	0.00	36.00	Cum	1	36.00	5.20	0.16	29.95		
	1st cros road (LHS)	0.00	45.00	Cum	1	45.00	6.50	0.16	46.80		
	2nd cros road (LHS)	0.00	70.00	Cum	1	70.00	4.50	0.16	50.40		
	3rd cros road (LHS)	0.00	65.00	Cum	1	65.00	5.80	0.16	60.32		
	4th cros road (LHS)	0.00	18.00	Cum	1	18.00	7.50	0.16	21.60		
	5th cros road (LHS)	0.00	96.00	Cum	1	96.00	5.80	0.16	89.09		
	7th cros road (LHS)	0.00	153.00	Cum	1	153.00	5.40	0.16	132.19		
	8th cros road (LHS)	0.00	56.00	Cum	1	56.00	5.40	0.16	48.38		
	9th cross road LHS	0.00	46.80	Cum	1	46.80	4.10	0.16	30.70		
	10th cros road (LHS)	0.00	28.50	Cum	1	28.50	5.30	0.16	24.17		

Sl. No.	Description of Work	Chainage from	Chainage to	Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
	Total								**647.12**	**5354.02**	**34,64,677.48**
14	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete. (PW,P& IWTD SR 2018-19, Pg No 27 Item No.5.30)										
	New Kerb										
	2nd A cross road	0.00	25.00	Nos	2	25.00			112.00		
	1st cross road (RHS)	0.00	26.00	Nos	2	26.00			116.00		
	2nd cross road (RHS)	0.00	26.00	Nos	2	26.00			116.00		
	3rd cross road (RHS)	0.00	26.00	Nos	2	26.00			116.00		
	4th cross road (RHS)	0.00	24.70	Nos	2	24.70			110.00		
	5th cross road (RHS)	0.00	36.00	Nos	2	36.00			160.00		
	1st cros road (LHS)	0.00	45.00	Nos	2	45.00			200.00		
	2nd cros road (LHS)	0.00	70.00	Nos	2	70.00			312.00		
	3rd cros road (LHS)	0.00	65.00	Nos	2	65.00			289.00		
	4th cros road (LHS)	0.00	18.00	Nos	2	18.00			80.00		
	5th cros road (LHS)	0.00	96.00	Nos	2	96.00			427.00		
	7th cros road (LHS)	0.00	153.00	Nos	2	153.00			680.00		
	8th cros road (LHS)	0.00	56.00	Nos	2	56.00			249.00		
	9th cros road (LHS)	0.00	46.80	Nos	2	46.80			208.00		
	10th cros road (LHS)	0.00	28.50	Nos	2	28.50			127.00		
	Total								**3302.00**	**435.84**	**14,39,132.16**
15	KSRRB M800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications,MORTH Chapter 8 (PW,P& IWTD SR 2018-19, Pg No 180, Item No. 24.1)										
	Kerb painting										
	2nd A cross road	0.00	25.00	Sqm	2	25.00	0.40		20.00		
	1st cross road (RHS)	0.00	26.00	Sqm	2	26.00	0.40		20.80		
	2nd cross road (RHS)	0.00	26.00	Sqm	2	26.00	0.40		20.80		
	3rd cross road (RHS)	0.00	26.00	Sqm	2	26.00	0.40		20.80		
	4th cross road (RHS)	0.00	24.70	Sqm	2	24.70	0.40		19.76		
	5th cross road (RHS)	0.00	36.00	Sqm	2	36.00	0.40		28.80		
	1st cros road (LHS)	0.00	45.00	Sqm	2	45.00	0.40		36.00		
	2nd cros road (LHS)	0.00	70.00	Sqm	2	70.00	0.40		56.00		
	3rd cros road (LHS)	0.00	65.00	Sqm	2	65.00	0.40		52.00		
	4th cros road (LHS)	0.00	18.00	Sqm	2	18.00	0.40		14.40		
	5th cros road (LHS)	0.00	96.00	Sqm	2	96.00	0.40		76.80		
	7th cros road (LHS)	0.00	153.00	Sqm	2	153.00	0.40		122.40		
	8th cros road (LHS)	0.00	56.00	Sqm	2	56.00	0.40		44.80		
	9th cros road (LHS)	0.00	46.80	Sqm	2	46.80	0.40		37.44		
	10th cros road (LHS)	0.00	28.50	Sqm	2	28.50	0.40		22.80		
	Total								**593.60**	**84.80**	**50,337.28**
	Removal of Unservicable soil, Loading, unloading and Cost of Haulage										
16	KSRRB M300-19 Removal of unserviceable soil including excavation, loading and disposal but excluding replacement by suitable soil which shall be paid separately as per clause 300.5 complete as per specifications MORTH Specification No. 301. (PW,P& IWTD SR 2018-19, Pg No 144, Item No.19.20)										
	Vide Item No 1			Cum					661.08		
	Total								**661.08**	**34.98**	**23,124.66**

Sl. No.	Description of Work	Chainage from	Chainage to	Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
17	KSRRB M-100-1 Loading and Unloading of Stone Boulder / Stone aggregate / Sand Kanker / Moorum.KSRRB M100-1 : Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications.MORTH -100 / Chapter 1, (PW,P& IWTD SR 2018-19, Pg No 136, Item No.17.1)										
	Vide Item No 8 & 9.			Cum	1				895.62		
									895.62	**57.00**	**51,050.17**
18	KSRRB M100-4.1. Cost of haulage Excluding Loading and Unloading MORTH-100/Chapter 1 case-I surface road (PW,P& IWTD SR 2018-19, Pg No 136, Item No.17.4)										
	Vide Item No 16 & 17.			Cum					1556.70		
	Total								**1556.70**	**51.28**	**79,827.54**
19	Filling in foundation with granite/trap broken metal 100mm and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead up to 50m and lift 1.5m complete as per specifications.										
	a) 40mm Jelly.			Cum	13	0.31 (3.142*0.63*0.63)/4		0.40	1.62	1901.00	**3081.86**
	b) 20mm Jelly.			Cum	13	0.31		0.40	1.62	1901.00	**3081.86**
	c) Coarse sand.			Cum	13	0.31		0.30	1.22	2651.00	**3223.31**
	d) Fine Sand			Cum	13	0.31		0.20	0.81	2651.00	**2148.87**
	e) 12.5mm chips			Cum	13	0.31		0.30	1.22	1901.00	**2311.39**
20	Supplying, laying and jointing HDPE pipes of specified grade and conforming to IS 4984- 995 with latest amendments and conveyingto work site including loading and unloading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub ends, flanged sets, bends, reducers etc. complete (Contractor will make his own arrangements for procuring water for testing) etc. for : HDPE Grade PE80-PN6.0, 630 mm dia. (Perforated Pipe for Rain Water Harvesting Pit) (BWSSB SR 2017-18, Pg No 121 Item No. 1.17 Code No. K010Q)										
	0.63m dia HDPE Perforated Pipe. For 1.8 Mtr depth,			Rmt	23.40				23.40		
									23.40	**10822.32**	**253242.32**

Sl. No.	Description of Work	Chainage from	Chainage to	Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
21	Providing of Geonets for Rain Water Harvesting pit on top of the filter media as specified in drawings or as approved by Engineer Incharge.										
				Sqm	12	0.31			4.05		
									4.05	71.03	287.88
									Total Cost		1,24,33,500.43
	KRIDL Charges @1 % On Construction cost										1,24,335.00
	GST at 12% of Tender Amount										14,92,020.05
	Preparation of DPR 1.0%										1,24,335.00
	PMC Charges & Quality Control Charges at 1.0%										1,24,335.00
	Miscellaneous & unforeseen charges										7,01,474.50
										GRAND TOTAL	1,50,00,000.00

Technically Sanctioned for Rs. ... (Rupees ... Only)
Under ... P-3727 SC-ST/TSP Mukyamantrijola Nava Bengalore / Nava Nagarathana Yojane
Job Code No. 212-00-05001-2
Registered as CE No. 59/19-20 Subject to conditions contained in Enclosed Memo No. CE(D)/TS/59/19-20 Dt. 16/11/2019
AE/JE: SI/Cadd FA 16/11 TS CE(D) 16/11/2019

i This work comes within BBMP limits
ii Certified that Personaly Inspected the Work Spot.
iii Certified that the estimate is prepared based on CSR of PWD Bangalore Circle 2018-19.
iv Estimate is prepared Making Use of essential item of work as per site Conditions in safest way of Execution in most economical way.
v This work is not included in any other program of work.

For Alcon Consulting Engineers (India) Pvt. Ltd.,

Authorised Signatory
Alcon Consulting Engineers (I) Pvt. Ltd., Bengaluru

Assistant Engineer,
Ward No-12
BBMP

Assistant Executive Engineer,
Shettyhalli/Dasarahalli/PIA/Hegganahalli Division
BBMP

Exceutive Engineer,
Dasarahalli Division
BBMP

ADMINISTRATIVELY SANCTIONED FOR Rs. 150.00
(Rupees One Hundred Fifty lakhs Only)
Under the Head of Acc... P-3727 SC-SP/TSP Mukyamantrijola Nava Bengalore / Nava Nagarathana Yojane
Registered ... 168/19-20 Subject to conditions ... memo No. EE/DD/A-1/168/1920 Dt. 14/11/2019
Exe. Eng
(DASARAHALLI) BBMP